

PEAB

PROJECT OVERVIEW

Customer: Wood&Hill AB

General Contractor: PEAB Sverige AB

Performed works: Plate Cast: April - June 2018

Address: Kålgårdsgatan 27, 553 23

Jönköping, Sweden Usage: Residential Volume: 2 300 m³ Area: 6 600 m²

CUSTOMER

Wood&Hill AB specialises in financing solutions for residential and commercial properties. Using their deep understanding of the industry's conditions, Wood&Hill AB creates opportunities construction for contractors and property developers to realise their ambitions, as a housing developer with focus а condominiums in expansive regions in southern and central Sweden.



CASE STUDY Residential



CHALLENGE

At the former Post-terminal in central Jönköping, on the eastern side of the city centre, the new, attractive residential district of Drotten is being created. General Contractor of the project, PEAB Sverige AB, was looking for a Concrete Contractor, who could make a watertight plate under a tight schedule.

Primekss with its High Performance Zero shrinkage concrete technology – PrīmXComposite was the best fit in the particular situation.

For the current project, extra unexpected ground preparation works were needed. As a result, the estimated overall construction time increased. The task of the Concrete Contractor was to make a plate with increased speed. 3 weeks were given for the preparation works, and for the concrete plate – only 1 week for casting.







SOLUTION

Despite the shortened time schedule Primekss was ready to do its best to finish the work in time and with the best quality. Primekss watertight concrete solution allows saving of time. As there was no need to install watertight membranes under the plate, a lot of time and resources were saved. It was estimated that by using the traditional concrete solution, execution would take 3 times longer.

It should be noted, that works on the building site were very well organised, meaning no interuption between different contractors and their works.











